



Saison DeLux

Exterior Restoration Services

Montreal & Surrounding Areas
Fully Insured · Professional Grade
Equipment

ESTIMATE

Date: June 20, 2024
Valid for 30 Days

Client: _____ Address: **3745 rue Orléans, Brossard** Surface Area: **500 sq ft** Crew: **1–2 workers**

SCOPE OF WORK

1. Site Inspection & Preparation

Inspect all driveway, sidewalk, and patio surfaces. Remove loose debris, leaves, and dirt. Protect nearby landscaping, windows, and doors. Identify damaged pavers, loose joints, or cracks before work begins.

2. Pre-Treatment – Techniseal Patio & Deck Cleaner

All hardscape surfaces are treated with Techniseal Patio & Deck Cleaner before pressure washing begins. Applied evenly and allowed to dwell per manufacturer recommendations. Loosens embedded dirt, moss, algae, mildew, lichen, and grime — improving cleaning effectiveness while reducing the pressure needed to protect surface integrity.

3. Professional Surface Cleaning

Commercial-grade pressure washing equipment with a rotary surface cleaner removes dirt, organic stains, moss, algae, mildew, surface discoloration, tire marks, and oil stains (where possible). Delivers a consistent, streak-free finish with minimal risk of surface damage.

4. Detail Pressure Washing

All edges, corners, expansion joints, steps, curbs, and hard-to-reach areas are pressure washed using specialized nozzles for a complete and uniform finish.

5. Weed Treatment

Once surfaces have dried, all paver joints are treated with a professional weed control solution (Roundup or equivalent) to eliminate existing weeds and inhibit future growth before new joint sand is installed.

6. Joint Preparation

Existing loose or deteriorated joint material is removed where necessary. All joints are cleaned thoroughly to ensure proper installation and bonding of the new polymeric sand.

7. Polymeric Sand Installation – SikaFast Fix

Premium polymeric sand is swept into all paver joints and compacted where necessary. Locks pavers together, reduces weed growth, discourages insects, minimizes erosion, and provides a clean finished appearance. Surface is blown clean and misted with water to activate the polymeric binders.

8. Final Inspection & Cleanup

All surrounding areas cleaned. Excess materials and debris removed. Final quality inspection performed. Client walkthrough available upon request.

DIRECT PROJECT COSTS

ITEM	QTY	ESTIMATED COST
Labor (1 day, 1–2 workers)		\$200.00
Polymeric Sand – SikaFast Fix	6 bags	\$240.00
Cleaning Chemicals & Degreaser		\$20.00
Total Operating Cost		\$460.00
Commission & Business Operations / Warranty Coverage		\$50.00
Profit		\$140.00
TOTAL		\$650.00

PAYMENT TERMS

DEPOSIT DUE UPON ACCEPTANCE**\$325.00**

Due upon written acceptance of this estimate

BALANCE DUE UPON COMPLETION**\$325.00**

Due upon completion of work, before the crew leaves the site

WARRANTY**1-Year Workmanship Warranty – Pressure Washing**

For one (1) year from the completion date, Saison DeLux warrants that all pressure-washed surfaces will be free from defects caused by improper cleaning technique. If a workmanship-related issue arises, we will re-clean the affected area or apply corrective treatment at no additional cost. Does not cover natural re-soiling, weather exposure, or damage caused by third parties.

2-Year Warranty – Polymeric Sand Joints

For two (2) years from the completion date, Saison DeLux warrants that polymeric sand joints will remain intact and free from defects caused by improper installation. If joint failure occurs due to installation error, we will repair or replace the affected joints at no cost. Does not cover damage from freeze-thaw settlement, heavy vehicle impact, or root intrusion.

TERMS & CONDITIONS

- Deposit of 50% is due upon written acceptance of this estimate. Balance is due upon completion.
- Quote valid for 30 days from the date of issue.
- Polymeric sand cannot be applied if rain is forecast within 24 hours of application — scheduling may be adjusted at contractor's discretion.
- Client is responsible for clearing vehicles and movable objects from the work area prior to the start date.
- Any pre-existing damage to pavers, underground utilities, or structures not disclosed prior to work is excluded from contractor liability.

Client Signature _____

Print Name: _____

Date: _____

Contractor – Saison DeLux _____

Print Name: _____

Date: _____

Thank you for choosing Saison DeLux. We look forward to restoring your property.